

PATENT

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re application of)	
Charles E. Friesner)	
)	
Application No: 09/723,312)	Art Unit: 3637
)	
Filed: November 27, 2000)	Examiner: Ms. Yvonne Michele Borton
)	
For: STRUCTURAL MEMBER)	Attorney Docket: 277.0017

Attached are copies of the applicant's file copy of Provisional Application 60/011,352, and of the filing receipt therefor. These are submitted in connection with the examination of the above-captioned application.

Respectfully submitted,

John C. Purdue
Reg. No. 16,555

JCPurdue
Purdue Law Offices
2735 N. Holland-Sylvania Road, Ste. B-2
Toledo, OH 43615-1844
Telephone: Voice (419) 531-0599
Fax (419) 531-0362


PROVISIONAL APPLICATION
FILING RECEIPT



UNITED STATES DEPARTMENT OF COMMERCE
Patent and Trademark Office
ASSISTANT SECRETARY AND COMMISSIONER
OF PATENTS AND TRADEMARKS
Washington, D.C. 20231

APPLICATION NUMBER	FILING DATE	FIL FEE REC'D	ATTORNEY DOCKET NO.	DRWGS
60/011,352	02/08/96	\$75.00	277.0007	11

PURDUE LAW OFFICES
2735 N HOLLAND SYLVANIA RD
SUITE B2
TOLEDO OH 43615-1844



Receipt is acknowledged of this Provisional Application. This Provisional Application will not be examined for patentability. Be sure to provide the PROVISIONAL APPLICATION NUMBER, FILING DATE, NAME OF APPLICANT, and TITLE OF INVENTION when inquiring about this application. Fees transmitted by check or draft are subject to collection. Please verify the accuracy of the data presented on this receipt. If an error is noted on this Filing Receipt, please write to Box Provisional Application within 10 days of receipt. Please provide a copy of the Provisional Application Filing Receipt with the changes noted thereon. This Provisional Application will automatically be abandoned twelve (12) months after its filing date and will not be subject to revival to restore it to pending status beyond a date which is after twelve (12) months from its filing date.

Applicant(s) CHARLES E. FRIESNER, PERRYSBURG, OH.

FOREIGN FILING LICENSE GRANTED 04/16/96
TITLE
STRUCTURAL MEMBER

* SMALL ENTITY *

TITLE

STRUCTURAL MEMBER

FIELD OF THE INVENTION

F.P. 2770007/277APP.1

This invention is a structural member and, in particular, is a structural member that was developed for use as a floor for a refrigerated or other truck or trailer, but can also be used as a roof for homes and commercial buildings, as floating and other docks and dock covers, as cross arms for utility poles, as steps, as walks and walkways, as seawalls, as fence posts, as patio decks, as building foundations, as beams, as structural panels, as windows, as piers, as outdoor furniture, as horse trailers, and as stalls and barnyard structures.

In another aspect, the invention is an intermediate composition that is admirably suited for use in producing the structural member described above, a Dyligomer, as defined below, which is used in formulating the foregoing intermediate composition, and a cured material that can be produced by subjecting the intermediate composition sequentially to condensation polymerization with an isocyanate and then to addition polymerization.

BACKGROUND OF THE INVENTION


Refrigerated trucks and trailers usually have aluminum floors made up of a number of extruded sections, each of which has a plurality of parallel, longitudinally-extending channels. Adjacent ones of the channels have common sidewalls, and webs which are parallel to one another and are structurally integral with opposite edges of the sidewalls. The sections are welded together to make an entire floor, which may have inside dimensions as great as 102 inches (2.6 meters) by 52½ feet (16 meters). The aluminum floor must be insulated from the metal of the truck or trailer by which it is supported. This is usually accomplished by attaching spaced transverse wooden members to the supporting metal of the truck or trailer, and attaching the aluminum floor to the wooden members. After the assembly is complete, a froth foam is injected from a wand into the spaces which are below the floor and between the wooden members, where the floor is unsupported. Such floors leak, and must be replaced frequently, to a large extent because movement of a trailer or truck while in operation on a highway often exerts enormous forces tending to strip screws that are supposed to hold the floor to the trailer or truck and, as a consequence, stripping frequently occurs after a short time of service. Wet floors are particularly subject to this stripping.

Isocyanates and compositions that are polymerizable by condensation of the NCO groups of isocyanates with compounds having active hydrogens have been used widely since World War II to produce a broad spectrum of products ranging from coating compositions to medical appliances.

BRIEF DESCRIPTION OF THE INSTANT INVENTION

The instant invention is based upon the discovery of a structural member made up of the aluminum floor described above, or another floor that is similar in design, but made of thinner aluminum or of another metal, and a cellular material having urethane groups in its molecular structure and an apparent density of at least 8 pounds per cubic foot (0.13 gm per cm³) bonded to the aluminum because of chemical affinity between the aluminum and the foam. As is subsequently explained in more detail, it is also desirable to compound the urethane to promote adhesion. As a consequence of its being in intimate contact with and bonded to the aluminum floor, the urethane foam supports the floor throughout its entire surface. Preferably, the structure also includes, as a substrate, a sheet of a second material, such as expanded polystyrene, plywood or the like, to which the urethane foam is also bonded because of the chemical affinity between the foam and the substrate. Most desirably, the second sheet is also the aluminum floor described above, with its parallel channels extending in a different direction than do the channels in the first floor, e.g., at right angles to the channels of the first floor. The structural member according to the invention has been found to be water tight and to have strength properties which indicate that it should have substantially extended service life by comparison with the previously described floor. The structural member can also be produced from sheet materials having the same shape as the aluminum floor, but made of metals other than aluminum, and can have various shapes other than that of the floor.

In another aspect, the instant invention is based upon the discovery of certain compounds, subsequently herein "Dyligomers", which can serve as monomers in a polycondensation reaction with a polyisocyanate and can also serve as monomers in an addition propagation reaction with an unsaturated cross linking monomer. These Dyligomers can be produced from diisocyanates, the triglyceride of ricinoleic acid, and such compounds as 1,3-propanediol, 1,4-butanediol and 1,4-but-2-enediol; they can be mixed with other compounds which have active hydrogens, are ethylenically unsaturated, or both, and fillers, catalysts, water and the like, and



the mixtures can be condensed to a thermoset condition with the same diisocyanate used to produce the Dyligomer, with another diisocyanate, or with a polyisocyanate. The thermoset condensate then cures further by addition polymerization involving the ethylenic unsaturation of the ricinoleic acid triglyceride or other ethylenically unsaturated compound moiety of the Dyligomer, or both. The triglyceride of ricinoleic acid, which is the principal constituent of castor oil, is an example of a

examples of compounds which are capable of undergoing both types of reaction include 1,2,3-trihydroxy propene, with three hydroxyl groups and one ethylenic double bond, 1,3-propene diol with two hydroxyl groups and one ethylenic double bond, and 1,4-but-2-ene diol, with two hydroxyl groups and one ethylenic double bond.


$$\begin{array}{c}
 \text{HO}-\text{CH}_2-\text{CH}=\text{CH}-\text{CH}_2 \\
 | \\
 \text{O} \\
 || \\
 \text{C} \\
 | \\
 \text{CH}_2-\text{CH}-\text{OC}(=\text{O})-\text{NH}-\langle \text{benzene ring} \rangle-\text{CH}_3 \\
 | \qquad | \\
 (\text{CH}_2)_5\text{CH}_3 \quad \text{OH} \\
 -\text{CHCH}_2\text{CH} \\
 | \qquad | \\
 \text{OH} \qquad (\text{CH}_2)_5\text{CH}_3 \\
 | \\
 \text{H}_2\text{C}-\text{CH} \\
 | \\
 (\text{CH}_2)_5\text{CH}_3
 \end{array}$$

3

THE PRIOR ART

"Cellular plastic products or plastic foams have been prepared in which isocyanates are used as one of the reactants * * *. In these products the cellular materials are prepared from alkyd resins which contain free carboxy groups."

$$\begin{array}{c}
 \text{CH}_2 - \text{O} - \overset{\text{O}}{\parallel}{\text{C}} - (\text{CH}_2)_7 - \text{CH} = \text{CHCH}_2\underset{(\text{CH}_2)_5\text{CH}_3}{\text{CH}} - \overset{\text{O}}{\parallel}{\text{O}}\text{C} - \text{NH} - \text{C}_6\text{H}_4 - \text{NCO} \\
 | \\
 \text{CH} - \text{O} - \overset{\text{O}}{\parallel}{\text{C}} - (\text{CH}_2)_7 - \text{CH} = \text{CHCH}_2\underset{(\text{CH}_2)_5\text{CH}_3}{\text{CH}} - \overset{\text{O}}{\parallel}{\text{O}}\text{C} - \text{NH} - \text{C}_6\text{H}_4 - \text{NCO} \\
 | \\
 \text{CH}_2 - \text{O} - \overset{\text{O}}{\parallel}{\text{C}} - (\text{CH}_2)_7 - \text{CH} = \text{CHCH}_2\underset{(\text{CH}_2)_5\text{CH}_3}{\text{CH}} - \overset{\text{O}}{\parallel}{\text{O}}\text{C} - \text{NH} - \text{C}_6\text{H}_4 - \text{NCO}
 \end{array}$$

4

by weight of a catalyst composed of di-n-octyltin bis(2-ethylhexyl thioglycolate) and mono-n-octyltin tris(2-ethylhexyl thioglycolate). The patent discloses the preparation of the modified MDI B component (NCO content of 23 percent by weight) by reacting 4,4'-MDI with a mixture of dipropylene glycol and a polyoxypropylene glycol having a hydroxyl number of 250.

US patent No. 5,290,632 discloses a Component A of a two component formulation as comprising castor oil and a low molecular weight polyol while component B is a polymeric MDI. An elastomer is an alternative constituent of component A. Examples of polymeric MDI's are said to be available from Dow Chemical under the registered trademark PAPPI 2027 (average molecular weight 340-380, average functionality 2.6-2.7) and under the designation "Mondur XP-744".

US patent No. 5,278,223 is concerned with the polyol component of a urethane formulation, which is required to include (1) branched chain polyols with ester and ether groups, (2) glycerol esters, e.g., castor oil and (3) low viscosity monofunctional alcohols of oleophilic character. The reaction of such a polyol constituent with technical methylene diphenyldiisocyanate "MDI", TDI or the like is disclosed.

US patent No. 5,166,301 discloses a prepolymer made from methane dicyclohexyl diisocyanate, a polyoxypropylene ether polyol, methane-dicyclohexyl diisocyanate and a silane, and reaction of the prepolymer with a component composed mainly of polyoxypropylene ether polyol and diethyltoluene diamine plus minor amounts of m-xylene diamine, organo-bismuth and water. Castor oil is named as a "hydroxy functional moiety".

US patent No. 5,157,101 discloses the reaction of liquid polyisocyanate from Mobay ("Mondur PF", 26.6 weight percent NCO) with polybutadiene polyols and amines.

US patent No. 5,155,165 discloses the reaction of isocyanates or an isocyanate terminated prepolymer with polyhydroxy compounds, which are broadly defined, by a process which produces "polyurethane polyurea particles" which can be, but are not necessarily, pigmented.

US patent No. 5,061,776 discloses a thermal transfer adhesive composed of 30 to 70 weight percent of an aliphatic diisocyanate or triisocyanate prepolymer, 5 to 15 weight percent of a polyether diol or triol, 20 to 40 weight percent of castor oil, 5 to 20 weight percent of an epoxy resin containing 2 or more hydroxyl groups and 0.006 to 0.008 weight percent of a catalyst for the reaction of isocyanate groups with hydroxyl groups. Dibutyl tin dilaurate is said to be the preferred catalyst.

US patent No. 4,990,586 discloses the production of a polyurethane by reaction between a polyisocyanate and a polyol in the presence of a diphenyl methane diamine with one amine group and either one or two alkyl group substituents on each phenyl. The preferred polyol is said to be castor oil.

US patent No. 5,021,535 discloses an abrasion resistant urethane composition for automobile undercoating made from unmodified castor oil and MDI-alkylene oxide prepolymers. The castor oil can be modified by an addition of a cyclohexanone-formaldehyde condensate and can be further modified by an addition of a neopentyl glycol adipic acid reaction product

US patent No. 4,990,586 discloses the production of a polyurethane by reaction between a polyisocyanate and a polyol in the presence of a diphenyl methane diamine with one amine group and either one or two alkyl group substituents on each phenyl. The preferred polyol is said to be castor oil.

US patent No. 4,987,204 discloses a coating composition "comprising 2-100 parts by weight of fluororesin, 5-100 parts by weight of a silicone oil, and a solvent to 100 parts of a urethane prepolymer * * * comprising a polyol, castor oil polyol, and a polyisocyanate * * *."

US patent No. 4,968,725 discloses a dental adhesive which includes a urethane prepolymer produced by reacting an isocyanate with a polyol (castor oil is named as an example), a "radical-polymerizable unsaturated monomer and a photopolymerization initiator, and can also include a polymerizable phosphoric ester.

US patent No. 4,877,829 discloses a "novel polyurethane resin" for application to exterior surfaces, including concrete roadways, produced from two components, Component A being composed of ricinoleic triglyceride (conveniently as castor oil) and a low molecular weight polyol (e.g., glycerol) and Component B being composed of either a mixture of MDI isomers or a mixture of MDI with a prepolymer made by reacting MDI with an alkylene oxide. An elastomer is an optional ingredient of the first component. A Table indicates the following ranges of ingredients in parts by weight to be workable: Castor oil 90 to 140, low molecular weight polyol 2 to 10 and Modified MDI 50 to 110. Up to 120 parts of an elastomer and up to 50 parts of molecular sieves can be used in the non-MDI Component A.

US patent No. 4,877,455 discloses the autoclaving of castor oil with dicyclopentadiene and hydroxyethyl methacrylate. A maximum temperature of 265° C. and a maximum pressure of 80 psi are reported. The product, which is called a graft polyol, when reacted with polymeric MDI (NCO/OH 1.05), produced a urethane said to be considerably more resistant to certain solvents by comparison with urethanes produced from the unmodified castor oil.

US patent No. 4,859,735 discloses "Novel polyurethane formulations especially useful as membranes of the protection of bridge deckings. The polyurethane is prepared by mixing two components, A and B. Component A comprises castor oil modified with a ketone-formaldehyde condensate and also preferably contains an elastomer. Component B is a modified MDI, being a

US patent No. 4,582,891 discloses a urethane coating composition. The urethane is produced from a polyol component composed of "a castor oil polyol alone or a mixture of a castor oil polyol and a low molecular weight polyol" and a polyisocyanate component. The "castor oil polyol" can be castor oil, an interesterification product of castor oil and ethylene oxide or the like, an esterification product of ricinoleic acid and an ethylene oxide or the like adduct of dipropylene oxide or the like. TDI and MDI are named as isocyanates. Dibutyl tin dilaurate is disclosed as a component of a polyol composition, along with castor oil.

US patent No. 4,555,536 discloses a polyurethane coating composition produced from (1) a polyol mixture of castor oil or a polyol derived from castor oil and an amine polyol produced by addition reaction of an alkylene oxide with ammonia, an aliphatic amine or the like, and (2) a polyisocyanate compound.

US patent No. 4,551,517 relates to a two-component polyurethane adhesive produced by mixing an isocyanate having a functionality of from 2 to 10 with a liquid mixture of anhydrous polyols having more than 10 carbon atoms and 2 or more hydroxyl groups, obtained by reacting (1) epoxidized higher fatty alcohols, (2) epoxidized higher fatty acid esters or (3) epoxidized higher fatty acid amides with aliphatic or aromatic alcohols having a functionality of 1 to 10, with difunctional or trifunctional phenols, or with both, with opening of the epoxide ring. Transesterification of the fatty acid esters, subsequent reaction with C2 to C4 epoxides, or both, is also disclosed. In two examples, the polyols are produced by ring opening epoxidized soy bean oil with methanol. Comparative examples are said to show the superiority of the adhesive of the invention over urethanes made from castor oil.

US patent No. 4,433,128 is directed to an embedding mass composed of a polyurethane obtained through reaction of an aromatic polyisocyanate with a mixture of castor oil and trimethylolpropane "pre-adduct" and a polypropyleneglycol or a mixture of a polypropyleneglycol and trimethylpropane in the presence of a catalyst which is a mixture of a dialkyl tin dicarboxylate and an aliphatic mono- or di-amine. The patent discloses the production of a Component A having an isocyanate content of 18.85 percent from a liquid polyisocyanate based upon MDI, castor oil and trimethylolpropane, the production of a Component B from polypropylene glycol, trimethylolpropane, dibutyl tin dilaurate and 1,4-diasabicyclo(2,2,2)-octane, and the mixing of the two components to produce casting resins. Several German patent applications are acknowledged as prior art, including DE-OS 28 13 197, which is said to disclose the production of "polyurethanes" by reacting an aromatic polyisocyanate with a mixture of castor oil and trimethylol propane to produce a pre-adduct, and polymerizing the pre-adduct with castor oil or a mixture of castor oil with trimethylol propane.

US patent No. 4,391,964 is directed to a potting medium composed of a polyurethane obtained through reaction of a polyisocyanate with a mixture of castor oil and trimethylolpropane "pre-adduct" and reaction of the prepolymer with castor oil or a mixture of castor oil with trimethylolpropane for cross linking. A titanium alkylate, e.g., titanium tetrabutylate, is used as a catalyst.

US patent No. 4,378,441 discloses resinous products produced by reacting (A) an alkali metal silicate, (B) an organic monohydroxy compound having a substituent which will split off during the reaction, and (C) a polycarboxylic acid and/or a polycarboxylic acid anhydride. Castor oil can be substituted for a small portion of the polycarboxylic acid.

US patent No. 4,375,521 discloses a vegetable oil extended polyurethane produced by reacting an isocyanate terminated polyisocyanate with a polyol (which can be castor oil) in the presence of a vegetable oil such as soybean, safflower, corn, sunflower, linseed, oiticica, coconut, cottonseed, peritta, palm, olive, rape or peanut

US patent No. 4,371,683 discloses that castor oil can be substituted for up to 85 percent of the polyol in an adhesive composed of the reaction product of a novolac, an oxirane and a polyisocyanate

US patent No. 4,344,873 is directed to a potting medium composed of a polyurethane obtained through reaction of a polyisocyanate with a mixture of castor oil and trimethylolpropane "pre-adduct" and reaction of the prepolymer with castor oil or a mixture of castor oil with trimethylolpropane for cross linking. A dialkyl tin compound is used as a catalyst.

U.S. Patent No. 4,170,559 discloses the production of a prepolymer (NCO content about 16.2 percent) from 204 g polyoxypropylene glycol (M.W. 400), 205 g castor oil and 795 g MDI, and cure of such a prepolymer with an ester of a polyhydric alcohol having 2 or three OH groups and an aliphatic acid having at least 12 carbons atoms and at least one OH group or epoxy group. The following U.S. patents are cited as disclosing the preparation of prepolymers: 2,625,531; 2,625,532; 2,625,535; 2,692,873; and 2,702,797.

The present inventor is not aware of any prior art disclosing Dyligomer I, above, or an equivalent thereof, i.e., a compound that has no NCO groups, and is composed of a chemical moiety that is derived from a diisocyanate, and is bonded through urethane groups to two additional chemical moieties which have a plurality of active hydrogens and a plurality of ethylenic double bonds so that they are capable of reacting with an isocyanate to form urethane linkages and, as a consequence, a three-dimensional cross linked polymer, and subsequently and independently, with a cross linking monomer in an addition propagation reaction. Accordingly, he is not aware of prior art disclosing an intermediate composition comprising such a Dyligomer and a cross linking monomer that is sufficiently fluid that fillers it may contain are wet effectively. Finally, he is not aware of prior art

disclosing a material that will cure to a thermoset condition which is produced by mixing an isocyanate with such an intermediate composition comprising Dyligomer I or an equivalent and a cross linking monomer.

OBJECTS OF THE INVENTION

Accordingly, it is an object of the invention to provide a Dyligomer which can serve sequentially as a monomer in a polycondensation reaction with a polyisocyanate and then as a monomer in an addition propagation reaction with an unsaturated cross linking monomer, because it has both ethylenic groups and active hydrogens in its molecule. The Dyligomer, as is subsequently explained in more detail, is composed of three chemical moieties, one of which is a moiety derived from a diisocyanate and is bonded to a first of the other moieties through a urethane group and to the second of the other moieties through a different urethane group.

It is another object to provide an intermediate composition composed of a Dyligomer, a cross linking monomer reactive by addition polymerization with the double bonds of the Dyligomer, a catalyst for the reaction of the Dyligomer with an isocyanate to form a urethane, and a free radical catalyst for the addition polymerization of the cross linker.

It is a further object to provide a thermoset material produced by condensing the intermediate composition with the diisocyanate used to produce the Dyligomer, with another diisocyanate, or with an isocyanate having more than two NCO groups per molecule.

It is yet another object of the invention to provide a thermoset condensate that has been cured further, after polycondensation, by an addition polymerization reaction involving the ethylenic unsaturation of the Dyligomer.

It is still another object to provide a structural member.

It is yet another object to provide a structural panel that is admirably suited for use as a floor in refrigerated trucks and trailers, and in roofs, sidewalls and load bearing walls for homes and commercial buildings.

It is still another object to provide structural members that are admirably suited for use as floating and other docks and dock covers, as cross arms for utility poles, as steps, as walks and walkways, as seawalls, as fence posts, as patio decks, as building foundations, as beams, as structural panels, as piers, as windows, as outdoor furniture, as horse trailers, and as stalls and barnyard structures.


BRIEF DESCRIPTION OF THE INSTANT INVENTION

In one aspect, the instant invention is based upon the discoveries that a Dyligomer that is stable for extended periods of time can be produced by reacting one molecule of a diisocyanate with two molecules, which can be the same or different, of a compound which has active hydrogens in its

Dyligomer I, as previously explained, can be produced by reacting one molecule of ricinoleic acid triglyceride with one molecule of 2,4-TDI, and one molecule of 1,4-but-2-ene diol. Dyligomer II, which has the following structure, is produced when one molecule of ricinoleic acid triglyceride reacts with one molecule of 2,4-TDI, and one molecule of glycerol:



11





that Dyligomers I



ing dyligomers can



where B is a chemical moiety formed by reactions involving the NCO groups of a diisocyanate having the formula,

OCN- B- NCO

and the active hydrogens of OH groups of compounds having the formulas

A -OH and D -OH

and A and D are chemical moieties formed by the reactions which formed B, and wherein A and D include, in their structures, at least two active hydrogens which are parts of OH groups and at least one ethylenic double bond. In addition, it will be appreciated that the properties of the Dyligomers represented by Formula I depend upon the identity of R. For example, Dyligomer IV has two OH groups and three ethylenic double bonds available for condensation polymerization with an isocyanate and for addition polymerization, respectively. However, the geometry of the molecule does not favor either type of reaction. Dyligomer I, on the other hand, has an additional ethylenic double bond and an additional OH group, and the geometry of the molecule favors reaction of both of the additional groups. As might be expected, available evidence indicates that Dyligomer I, by comparison with Dyligomer IV, is capable of a higher degree of condensation polymerization with an isocyanate and of a higher degree of addition polymerization with a cross-linking molecule. Similarly, Dyligomer II and Dyligomer III appear to be capable of a higher degree of condensation polymerization with an isocyanate.

Dyligomers can also be produced from:

- (A) other diisocyanates, the triglyceride of ricinoleic acid, and n-butanol, 1,4-butane diol, glycerol, 1,2,3-trihydroxy propene, and 1,4-but-2-ene diol,
- (B) diisocyanates, the triglyceride of ricinoleic acid and various polyesters and polyethers having free alcoholic OH groups (such polyesters and polyethers are commercially available, and are sold for use in producing urethanes), and
- (C) diisocyanates, n-butanol, 1,4-butane diol, glycerol, 1,4-but-2-ene diol, 1,2,3-trihydroxy propene, various polyesters and polyethers having free alcoholic OH groups (such polyesters and polyethers are commercially available, and are sold for use in producing urethanes) and equivalents for the triglyceride of ricinoleic acid.

Examples of compounds which can be used as equivalents for the ricinoleic acid triglyceride in producing Dyligomers include ricinoleic and other fatty acid monoglycerides, ricinoleic and other fatty

acid diglycerides and fatty acid esters of various polyesters and polyethers having free alcoholic OH groups, for example, ones which are commercially available for reaction with isocyanates to produce urethanes; and fatty acid monoesters of glycols, and of fatty acid esters which have at least one free alcoholic OH group, and are formed by esterification of alcoholic OH groups of various polyesters and polyethers with fatty acids.

In theory, it is possible to produce Dyligomers from diisocyanates, n-butanol, 1,4-butane diol, glycerol, 1,4-but-2-ene diol, various polyesters and polyethers having free alcoholic OH groups (such polyesters and polyethers are commercially available, and are sold for use in producing urethanes) and fatty acids. As a practical matter, however, it is necessary to control the rates of reaction between the diisocyanate and the fatty acid, and between the diisocyanate and the n-butanol or the like so that Dyligomers composed of moieties from all three reactants are formed.

The foregoing and other dyligomers can be mixed with a cross linker such as styrene, diallyl phthalate, triallyl cyanurate, a free radical catalyst and a catalyst such as cobalt naphthenate for the condensation of an isocyanate with a reactive hydrogen of an OH group to produce an intermediate that is stable for extended periods of time, and can be mixed with a diisocyanate or a polyisocyanate to produce a polymerizable composition in which the dyligomers and the diisocyanate or polyisocyanate undergo condensation polymerization to form urethane linkages and a three dimensional cross linked polymer and, subsequently and independently, the dyligomer reacts with the cross linker in an addition propagation reaction. The intermediate composition can also contain various fillers, a colorant, and water, if a cellular product is desired.

BRIEF DESCRIPTION OF THE DRAWINGS

Fig. 1 is a schematic diagram showing apparatus which can be used to produce a structural member according to the invention.

Fig. 2 is a vertical sectional view showing a mold which is a part of the apparatus of Fig. 1 with an aluminum floor of the kind described above positioned in the mold.

Fig. 3 is a view in vertical section similar to Fig. 2, but showing the mold and aluminum floor after a foamable polyol/isocyanate or the like composition has been introduced into the mold.

Fig. 4 is a vertical sectional view similar to Fig. 3, but showing the mold in a closed position and a sheet of expanded polystyrene or the like on top of the foamable polyol/isocyanate or the like composition.

Fig. 5 is a view in vertical section similar to Fig. 4, but showing the assembly after the polyol/isocyanate composition has foamed so that it is confined within the closed mold between the expanded polystyrene or the like sheet and the aluminum floor.

Fig. 6 is a perspective view showing the structural member which is produced after cure of the polyol/isocyanate composition of Figs. 3-5 to a foamed, thermoset condition.

Fig. 7 is a vertical sectional view of the aluminum floor of Figs. 2-6, showing a typical longitudinally extending joint between two adjacent lengths of the material.

Fig. 8 is a view in vertical section taken along the line 8-8 of Fig. 6, and showing further details of the structural member.

Fig. 9 is vertical sectional view showing another embodiment of a structural member according to the invention.

Fig. 10 is a view in vertical section showing still another embodiment of a structural member according to the invention.

Fig. 11 is a vertical sectional view similar to Fig. 3, illustrating an intermediate stage in the production of yet another embodiment of a structural member according to the invention; Fig. 11 shows a mold, two aluminum floors and a foamable polyol/diisocyanate composition in the mold.

Fig. 12 is a view in vertical section showing the mold and the aluminum floors of Fig. 11 after the foamable composition shown in that view has expanded and cured to a urethane.

Fig. 13 is a view in vertical section taken along the line 13-13 of Fig. 12, and showing the relationships among the two aluminum floors and the foamed urethane.

Fig. 14 is a fragmentary, vertical sectional view showing the final product, which is one of the presently preferred structural members according to the invention, which is produced from the intermediates of Figs. 12 and 13; the member is shown situated in a mold which is also shown in Figs. 11 through 13.

Fig. 15 is a fragmentary view in vertical section showing another of the presently preferred structural members according to the invention; the member is shown in a mold in which it can be produced.

Fig. 16 is a fragmentary, horizontal sectional view showing still another of the presently preferred structural members according to the invention; the member, which can be used as a fence post is shown in a mold in which it can be produced.

Fig. 17 is a view in vertical section taken along the line 17-17 of Fig. 16.

Fig. 18 is a fragmentary, vertical sectional view showing yet another of the preferred structural members according to the invention.

Fig. 19 is a view in vertical section taken along the line 19-19 of Fig. 18.

Fig. 20 is a plan view of a part of a mold that has been used to produce a strip of cured material about 8 feet long, 4 inches wide and $\frac{1}{2}$ inch thick.

Fig. 21 is a view in elevation showing the mold part of Fig. 20 with a first cover on the mold part.

Fig. 22 is an elevational view showing the mold part of Fig. 20 with a second cover on the mold part.

Fig. 23 is a front view in elevation showing a window frame according to the invention; the frame has opposed side guides, an upper stop and a sill.

Fig. 24 is sectional view taken along the line 24-24 of Fig. 23, and showing the structures of the opposed side guides of the Fig. 23 window.

Fig. 25 is a view in section taken along the line 25-25 of Fig. 23, and showing the structure of the sill of the Fig. 23 window.

Fig. 26 is a view in front elevation showing a mold in which the window of Fig. 23 can be produced.

Fig. 27 is a view showing the mold of Fig. 26 in a position in which a polymerizable composition according to the invention can be poured into the mold to produce the window of Fig. 23.

Fig. 28 is an elevational view showing the window frame of Fig. 23 mounted in a fragment of a stud wall of a building.

DESCRIPTION OF THE PREFERRED EMBODIMENTS

Example 1, below, describes the production of Dyligomer I. In Example 1, and elsewhere herein, the terms "parts" and "percent" refer to parts and percent by weight, unless otherwise indicated. The following abbreviations are used: cm means centimeter or centimeters; g means gram or grams; kg means kilogram or kilograms.

Example 1

Dyligomer I was produced from castor oil which had an assay of 89 percent ricinoleic triglyceride, a hydroxy No. of 161 to 169 and an iodine No. of 81 to 89, an isomer blend of 80 percent 2,4-TDI and 20 percent 2,6-TDI, 1,4-but-2-ene diol and dibutyltin dilaurate. The TDI had an NCO content of 50 percent. The castor oil, the dibutyltin dilaurate, and the 1,4-but-2-ene diol were metered into a first static mixer in such proportions that the weight ratio of the castor oil to the 1,4-but-2-ene diol to the dibutyltin dilaurate flowing in the mixer was 930:88:2.5. The effluent from the first static mixer and the TDI were metered into a second static mixer in such proportions that the weight ratio of the castor oil to the 1,4-but-2-ene diol to the dibutyltin dilaurate to the TDI in the second mixer was 930:88:2.5:168. The effluent from the second static mixer was a homogeneous solution which contained Dyligomer I and had an NCO content less than 10 parts per million; the solution was stable, and has been stored at ambient temperature of about 25° C. for extended periods

of time without visible sign of phase separation or of change in viscosity. The solution had an OH content of 4.29 percent. There was no refraction of a beam of light shined through the solution.

An intermediate composition was then prepared by thorough mixing of 100 parts of the Dyligomer I solution, 28.1 parts of triallyl cyanurate, 1 part of benzoyl peroxide, 1.5 parts of cobalt naphthenate, 1 part of dimethyl aniline, 1.2 parts of a silicone surfactant that is commercially available from Dow Corning under the designation DC 193, 90 parts of 5 micron calcium carbonate (325 mesh), 0.5 part of water and 1 part of a polymeric colorant.

A mixture of the intermediate composition and a liquified MDI were then used to produce a structural member according to the instant invention which is indicated generally at 10 in Fig. 6. The member 10 is composed of an aluminum floor 11, a cured cellular body 12 of a thermoset material according to the invention, and an expanded polystyrene sheet 13. The member 10 can be produced in a mold 14 (Fig. 2) which has sidewalls 15, a bottom 16 and a top 17 which is attached to one of the sidewalls 15 by a hinge 18. Producing the member 10 involved placing the aluminum floor as indicated generally at 19 on the bottom 16 of the mold 14, introducing a predetermined quantity of a mixture of liquefied MDI and the intermediate composition produced as described above into the floor 11 inside the mold 14, placing the expanded polystyrene sheet 18 on top of the mixture, and closing the top 17 of the mold 14. The mold 14 is shown in Fig. 3 with a quantity of the MDI/intermediate composition, designated generally at 20, inside the aluminum floor 19, in Fig. 4 with the expanded polystyrene sheet 13 on top of the MDI/intermediate composition 20 and with the top 17 closed, and in Fig. 5 after the composition 20 has foamed and cured so that it is the thermoset foam 12. As an incident of the foaming of the composition 20, the expanded polystyrene sheet 13 has been forced against the top 17 of the mold 14 and the foaming composition has been forced into intimate contact with the aluminum floor 11 and with the expanded polystyrene sheet 13.

There are openings (not illustrated) through the expanded polystyrene sheet; during foaming, expansion of the composition 20, forces the polystyrene sheet into contact with the mold top, and further expansion forces the foaming composition into and to the tops of the openings, so that the composition can be seen as part of the upper surface of the structural member 10 (Fig. 6, where a pad composed of the thermoset foam which fills one of the openings is designated 21). The pads 21 which extend through to the upper surface (in Fig. 6) of the expanded polystyrene sheet 13 are an important part of the structural members 10. The structural members, when in service as the floor of a refrigerated truck or trailer, are inverted from the position shown in Fig. 6, so that the pads 21 bear on the support members of the truck or trailer, and can be secured in place by screws which extend through the support members, but are thermally insulated by the thermoset foam of the pads 21 from the aluminum of the structural members.

The mixture of the liquefied 4,4'-MDI and the intermediate composition of Example 1 was produced in the apparatus of Fig. 1. The MDI was charged to a vessel 22 (Fig. 1), and the intermediate composition was charged to a vessel 23. The MDI was then pumped from the vessel 22 through a line 24 to a meter 25, while the composition in the vessel 23 was pumped from the vessel 23 through a line 26 to the meter 25, which was set to deliver the MDI at a rate of 44.6 parts per minute and the intermediate composition in the vessel 23 at a rate of 100 parts per minute through a line 27 to a mixer 28 where they were rapidly and thoroughly mixed before being discharged through a line 29 into the mold 14 (see, also, Fig. 2). The MDI introduced into the line 29 contained substantially 1.05 NCO groups per OH group in the intermediate composition introduced into the line 29. Parts of the inner surfaces of the sides 15 of the mold 14 (see Figs. 2-5) were in contact with the MDI/intermediate composition introduced into the mold 14, and during and after foaming; these surfaces had been sprayed with a 5 percent solution in naphtha of a silicone caulking material that is commercially available from Dow Corning under the designation Silicone II. The aluminum floor in the mold 14 had a wall thickness of 0.08 cm; the horizontal surfaces 30 thereof were 2.14 cm wide, from left to right in Fig. 2. All of the other horizontal surfaces of the floor 19 were 2.54 cm wide, from left to right in Fig. 2, and all of the vertical surfaces thereof were 2.54 cm high. The mold 14 was charged, in about 10 seconds, with 568 g of the composition flowing from the line 28 per 929 cm² of aluminum floor surface, disregarding the area of the legs which extend vertically in Fig. 2 and the area of the horizontally extending surfaces which face downwardly in Fig. 2. The sheet 13 of expanded polystyrene, which fills the mold from right to left as shown in Fig. 4 and, in a similar manner, from front to back, was then placed on top of the foamable composition as shown in Fig. 4, and the lid 17 of the mold 14 was closed, and clamped shut. The foamable composition expanded to force the expanded polystyrene sheet into contact with the lid 17 of the mold 14, and forced itself into intimate contact with the bottom of the expanded polystyrene sheet and with the surfaces of the aluminum floor 19 which were exposed to it.

As is noted above, there were openings in the expanded polystyrene sheet 13 when it was placed in the mold 14. During foaming of the composition, vapor phase components escaped through these openings and from the mold 14, and the foaming composition forced itself into and through the openings, forming the pads 21 (Fig. 6) into which screws or other threaded members can be turned to attach the structural member 10 to structural parts of a trailer, truck, roof or the like. Since the upper surfaces of the pads 21 were in contact with parts of the lid 17 of the mold 14, those parts of the lid had also been sprayed with the Silicone II solution described above. The openings into which the foaming composition forces itself to form the pads 21 are provided at least as frequently as necessary to enable the escape of air and vapors from the mold and to provide pads wherever they are

needed, e.g., every 12 inches, every 18 inches or every 24 inches, longitudinally of the member 10. It is customary, in floors for refrigerated trucks and trailers, to provide cross supports every 12 inches; in this case, there should be pads 21 every 12 inches, and there should be at least two, and usually three across the width of the floor.

The aluminum floor 19 is commercially available, and, like wood, has sufficient strength that it can be used as a flooring material in trucks and trailers, being capable of supporting fork trucks driven into the trucks or trailers. It is known that the aluminum floor has higher compressive and flexural strengths and a higher modulus of rupture than hardwood, and that the structural member 10 has higher compressive and flexural strengths and a higher modulus of rupture than the aluminum floor 19. The structural member 10 is also significantly superior to hardwood as a thermal insulating material, and can be made as thick as desired, within relatively wide limits, to provide the desired thermal insulating capability.

The liquefied 4,4'-DMI is commercially available from BASF under the trade designation Lupranate M20S. It contains 2.15 NCO groups per methylene group. A similar material is available from Mobay under the designation Mondur MR. Such materials can be produced by reacting 4,4'-MDI having a slightly higher ratio of NCO groups to methylene groups with a small amount of a polyethylene glycol having a molecular weight of about 400. The reaction lowers the NCO to methylene group ratio to 2.15, and produces a homogeneous solution, which is, essentially, a prepolymer.

The polymeric colorant used as described in Example 1 was one that includes a chromoform chemically bonded to an OH group, and is commercially available from Milliken Chemicals, Spartanburg, South Carolina under the trade designation REACTINT. The hydrogen of the OH group is active, so that it reacts with a free NCO group of the polymerizable composition, with the result that the colorant is chemically bonded to the cured material.

The static mixer used in the procedure described in Example 1 is commercially available from TAH Industries, Inc., under the trademark STATA-TUBE mixer. It is disclosed in U.S. patent No. 4,093,188. The same company markets another mixer under the trademark SPIRAL mixer, which is also suitable. This mixer is disclosed in U.S. patents No. 4,840,493 and No. 4,850,705.

An aluminum member having the shape of the floor 19, but made from thin sheet material, was used to produce a structural member similar to a part of the member 10. The specific member used was so thin that, when it was suspended between two supports which extended transversely of its channels, and were separated from one another by twelve inches, a load applied in the center of the member caused it to collapse before available instrumentation indicated the magnitude of the load. An identical aluminum member was then placed in the mold 14 (Fig. 1); the mold was charged with

568 g per 929 cm² of the intermediate/isocyanate composition produced as described above with reference to Fig. 1; a sheet of thin polyethylene was placed over the foamable composition; a sheet of expanded polystyrene was placed in the mold, above the polyethylene sheet; and the lid 17 was closed, and clamped shut. The composition expanded to fill the available space inside the mold 14, and cured to such an extent that it could be removed from the mold after about 10 minutes; it had an apparent density of about 20 gm per cc. After the foamed composition had cured for about 48 hours, the member, when it was suspended between two supports which were circular in cross section and extended transversely of its channels, and were separated from one another by twelve inches on centers, withstood a load of 4560 pounds before failure. The load was applied by a member that was circular in cross-section, that extended laterally across the structural member, and that was spaced six inches on centers from each of the supports. A sharp noise from the member was deemed to indicate failure; it was determined that the foam had pulled away from the metal, and that the metal had collapsed.

The procedure described in the previous paragraph was repeated, except that the aluminum member was lined with a thin polyethylene sheet before the foamable composition was poured therein. The polyethylene sheet prevented the foam from adhering to the aluminum so that a body of the foam could be removed from the mold after foaming and initial cure. After the foam had cured for about 48 hours, it was suspended as described above and subjected to a load applied as described. Failure occurred at an applied load of 700 pounds.

The aluminum floor 19 comes in 25.4 cm widths, and with outer channels which can be forced together as shown in Fig. 7 to connect adjacent lengths of the material to one another. The floor 19, as described above, has been used in refrigerated and dry cargo trucks and trailers, and wood has been used in dry cargo trucks and trailers. It has been found that the floor 19 is stronger than wood in this service. Malaysian Kapur, a hardwood that has been found to be suitable for this use, has been found to have a flex strength of 2433 pounds and the following properties:

Physical property	Test Method	Value
Compressive Strength	D1621	3880 psi.
Screw holding resistance: initial	SE14	1865 pounds
fatigued	E14	318 pounds

A typical urethane foam having a density of 36 pounds per cubic foot (0.58 g per cm³) had a flex strength of 1806 pounds per square inch and a Screw holding resistance of 1510 pounds initial, and 1504 pounds, fatigued (Test Methods SE14 and E14). The tests described above indicate that the structural member 10 has a greater compressive strength and a greater flex strength than does the floor 19. Therefore, the member 10 has excess strength for use as a floor for a refrigerated or dry cargo

truck or trailer, which means that a member 10 made with a floor having thinner walls would have the requisite strength. In general, for use as a floor for a refrigerated truck or trailer, the structural member should have a compressive strength of at least about 3500 psi. and flex strength of at least about 2000 pounds. For use as a roof, the member 10 needs only the strength requisite to support a snow load, which is only a few pounds per square inch even for several feet of snow. The structural member 10 can also be used as a sea wall, as a floating dock or as one which rests upon and may be attached to suitable supports, as a foundation for a house or other building, or as a wall or ceiling panel. The thickness of the walls of the aluminum floor 19 and the apparent density of the foam can be varied as necessary to provide the required strength and other properties needed for any of the above uses. In general, increasing the thickness of the walls of the aluminum floor or the amount of foamable composition charged, other factors being equal, increases the strength of the structural panel, and vice versa. Similarly, decreasing the amount of urethane composition charged decreases the weight of the structural member, and substituting another foamable composition for the urethane material changes the strength properties and, usually, the apparent density of the thermoset foam that is produced. A decorative finish can be provided on one or both of the major surfaces of the structural member so that it can be used as an insulating wall panel that is pre-decorated on one or both sides.

The method described above in Example 1 has been used to produce other dyligomer solutions from the TDI isomer blend described above. Representative ones of the starting materials that were used, and the quantities in parts, are set forth in the following table:

	TDI	Castor Oil	2-butene-1-ol	1,4-but-2-ene diol	Glycerol
Example 2 ¹	168	930	72	--	--
Example 3 ²	168	930	--	--	92
Example 4 ²	168	--	--	176	184
Example 5 ²	168	--	144	--	184

¹also contained 2.5 parts of dibutyl tin dilaurate and 1.5 parts of stannous octoate

²also contained 2 parts of stannous octoate

Dyligomers can also be produced by the procedure of Example 1 from other isocyanates, preferably diisocyanates, for example, from other isomer blends of TDI, from pure 2,4-TDI or from pure 2,6-TDI, from 1,6-hexamethylene diisocyanate, from m-xylene diisocyanate, from dianisidine diisocyanate, from isophorone diisocyanate and from tolidine diisocyanate. An equivalent amount of the other diisocyanate is merely substituted for the TDI isomer blend in the Example 1 procedure.

Pure MDI is difficult to use as a starting material in producing urethanes and Dyligomers

according to the instant invention because it is a solid at room temperature. A prepolymer that is a liquid at room temperature and is produced by reacting MDI with a low molecular weight polyethylene glycol or similar material is usually employed as a starting material in producing urethanes containing MDI moieties. Such prepolymers frequently contain more than two NCO groups per molecule and, for that reason, are relatively undesirable starting materials for producing a Dyligomer according to the invention, because the Dyligomers are preferably liquids of low viscosity which are free of NCO groups. If all the NCO groups of the prepolymers are reacted, cross linking occurs, and the viscosity of the product is increased as a consequence.

Examples, in parts, of another intermediate composition that can be produced from Dyligomer I and of intermediate compositions that can be produced from the Dyligomers of Examples 2 through 4 are set forth in the following table. Each intermediate composition was produced from 100 parts of the indicated Dyligomer, 1 part of the previously identified colorant, 1 part of dimethyl aniline, and the amount in parts of the other ingredients listed in the table, where "TAC" means triallyl cyanurate, "DAP" means Diallyl phthalate, "BP" means benzoyl peroxide, "t-BPB" means t-butyl peroxybenzoate, and "CoNaph" means cobalt naphthanate.


	Int II	Int III	Int IV	Int V
Dyligomer	I	Ex 2	Ex 3	Ex 3
TAC	--	--	21.2	--
DAP	40.2	--	--	15.6
Styrene	--	34.0	--	12.2
BP	1.0	--	--	--
t-BPB	--	2.0	2.0	2.0
CoNaph	1.5	2.0	2.0	2.0
CaCO ₃	20	20	--	80
Water	--	--	1.0	0.7
DC 193	--	--	2.0	1.5

	Int VI	Int VII	Int VIII	Int IX
Dylogomer	Ex 4	Ex 4	Ex 4	Ex 5
TAC	--	15.4	--	--
DAP	--	--	22.6	19.7
Styrene	18.5	--	--	--
BP	1.5	--	2.0	1.5
t-BPB	2.0	2.0	--	--
CoNaph	2.0	2.0	1.5	1.5
CaCO ₃	--	60	150	100
Water	0.5	--	0.4	0.6
DC 193	0.5	--	0.5	0.5


Polymerizable compositions according to the invention can be produced by mixing any of intermediate compositions 2 through 9 with an appropriate amount of the previously identified liquefied MDI or of another polyisocyanate. The amount of the solubilized MDI that is appropriate for mixture with 100 parts of Intermediate II is 60.5, with 100 parts of Intermediate III is 31.0, with 100 parts of Intermediate IV is 53.1, with 100 parts of Intermediate V is 30.2, with 100 parts of Intermediate VI is 104.7, with 100 parts of Intermediate VII is 72.4, with 100 parts of Intermediate VIII is 47.1, and with 100 parts of Intermediate IX is 92.3

Preferred starting materials that have been used in producing Dylogomers according to the instant invention are named below; their molecular weights and the number of ethylenic double bonds, and of OH groups or of NCO groups per molecule are given parenthetically after their names: 2,4-TDI and 2,6-TDI, (174, 2 NCO groups per molecule, no ethylenic double bond), glycerol (92, 3 OH groups per molecule, no ethylenic double bond), ricinoleic acid triglyceride (981.4, 3 OH groups and 3 ethylenic double bonds per molecule), 1,4-butane diol (90.12, 2 OH groups per molecule, no ethylenic double bond), ethylene glycol (62.07, 2 OH groups per molecule, no ethylenic double bond), 1,3-propane diol (76.1, 2 OH groups per molecule, no ethylenic double bond), but-2-ene-1,4-diol (88.12, 2 OH groups and 1 ethylenic double bond per molecule), 2-butene-1-ol (72.12, 1 OH group and 1 ethylenic double bond per molecule) and sorbitol (182.17, 6 OH groups per molecule, no ethylenic double bond). Hexamethylene diisocyanate (168.21, 2 NCO groups per molecule, no double bond) and 4,4'diphenylmethane diisocyanate (263.54, 2.3 NCO groups per molecule, no ethylenic double bond), can be substituted for the TDI isomer mix. Similarly, other ethylenically unsaturated monomers, e.g. styrene and diallyl phthalate, can be substituted for the triallyl cyanurate in the foregoing intermediate compositions; the amount of the other unsaturated compound should introduce


the same number of ethylenic double bonds for a similar polymerized material. The structures of the foregoing starting materials, unless previously set forth, are given below, identified by legends:




2,4-toluene diisocyanate





2,6-toluene diisocyanate




Glycerol




1,3-propane diol




Hexamethylene diisocyanate




Sorbitol




2-Butene-1-ol




4,4' diphenylmethane diisocyanate




Tri allyl cyanurate




Styrene




Diallyl Phthalate



Isophorone
Diisocyanate





o-Tolidine Diisocyanate



m-Tolidine Diisocyanate

Castor oil contains about 85 to 90 percent of ricinoleic acid triglyceride and small amounts of glycerides of other fatty acids, for example, oleic and linoleic, which have the following formulas:




It will be noted that the oleic acid, the linoleic acid, and the other impurities that are normally present in castor oil were not removed before Dyligomer I was produced as described in Example 1. These materials are not detrimental in the final product; indeed, it is not necessary to purify the diisocyanate, because entirely satisfactory results, in terms of the final product and its properties, can be produced from isomer mixes that are commercially available. Dyligomer I is a liquid in which the constituents of the castor oil in addition to the ricinoleic acid triglyceride and the non-isocyanate constituents of the TDI are soluble. In the Example 1 procedure, assuming that one molecule of TDI reacted with one molecule of ricinoleic acid and one molecule of but-2-ene diol, the amount of TDI charged to the second static mixer in a given unit of time was sufficient only to react with most of the ricinoleic acid triglyceride and of the 1,4-but-2-ene diol charged in that unit of time. As is noted above, however, the reaction product was a homogeneous liquid in which there was no sign of phase separation after prolonged standing. It has been found that a relatively small increase in the proportion of TDI charged to the second static mixer will cause a substantial increase in the viscosity of the reaction product, but that the proportion can be decreased substantially below that charged in the procedure of Example 1 without causing a significant decrease in viscosity. It will be appreciated that the low viscosity of the Example 1 Dyligomer solution is advantageous because it contributes to the

effective wetting of fillers. Castor oil and 1,4-but-2-ene diol are immiscible in most proportions, including those in which they were used in the Example 1 procedure. Furthermore, if castor oil, dibutyl tin dilaurate and 1,4-but-2-ene diol are charged in the proportions in which they were used to produce Dyligomer I to a reaction vessel and stirred vigorously while gradual additions of TDI or another diisocyanate are made until the proportion of diisocyanate used in the Example 1 procedure has been added, reaction proceeds in an uncontrollable manner, and produces a gelatinous mass whose properties vary from batch to batch, and which is probably composed of a solid prepolymer dissolved in unreacted starting materials. However, when 2,4-TDI was added slowly to a vigorously stirred mixture of 930 parts of castor oil and 89 parts of 1,4-but-2-ene diol until a total of 42 parts of TDI had been added, and the dibutyl tin dilaurate was then added, a solution was produced which had about the same viscosity as the Dyligomer I solution of Example 1, and was a homogeneous single phase.

The solution of Dyligomer I produced as described in Example 1 is effective for introducing both castor oil and 1,4-but-2-ene diol into the intermediate composition produced therefrom as described above. Because castor oil and 1,4-but-2-ene diol are immiscible in the proportions in which they are desired in the intermediate composition, it is not feasible to prepare an intermediate composition from castor oil and 1,4-but-2-ene diol, triallyl cyanurate, benzoyl peroxide, cobalt naphthenate, dimethyl aniline, the DC 193 silicone surfactant, 5 micron calcium carbonate, water and the polymeric colorant, and then to react that intermediate with an appropriately increased amount of a diisocyanate or of a polyisocyanate. It will be appreciated, however, that the active hydrogen content of the dyligomer solution produced by reacting castor oil and 1,4-but-2-ene diol with 2,4-TDI or with another diisocyanate can vary within rather broad limits. For example, as noted above, ricinoleic acid triglyceride has three OH groups with hydrogens that are at least potentially active and three ethylenic double bonds, while 1,4-but-2-ene diol has two OH groups with active hydrogens and one ethylenic double bond. When the Dyligomer is one produced by the reaction of one molecule of 2,4-TDI with one molecule of ricinoleic acid triglyceride and one molecule of 1,2-but-2-ene diol, the Dyligomer has three active hydrogens (two from the ricinoleic acid triglyceride and one from the 1,4-but-2-ene diol) and four ethylenic double bonds. The reaction of one molecule of an isocyanate with the dyligomer reduces the active hydrogens by one, while the copolymerization of one molecule of a copolymerizable monomer having an ethylenic double bond with one molecule of the dyligomer reduces the number of ethylenic double bonds by one, but produces a group which is capable of further addition polymerization with a copolymerizable monomer having an ethylenic double bond. The amount of a diisocyanate or of a polyisocyanate mixed with the intermediate composition of Example 1, or with another intermediate composition, should introduce from substantially 1.0 to 1.1,

Diisocyanates other than 2,4-TDI form products analogous to that shown above for the several Dyligomers, except for the positions, numbers, or both of the urethane groups. For example, 2,4,6-toluene triisocyanate would produce a product with a third urethane group, while a monoisocyanate would produce a product with only one urethane group, and the other diisocyanates would produce products where the position of at least one of the urethanes is different. Dyligomer III is the compound that is produced when castor oil, 2,4-TDI and 1,4-butane diol are reacted in such proportions that, for every three OH groups in the castor oil, there are two NCO groups in the diisocyanate and two OH groups from the 1,4-butane diol. The following dyligomer can also be produced from castor oil, 2,6-TDI and 1,4-butane diol:



30

polyisocyanate and a lesser capability of addition copolymerization. Dyligomers III and IV have the same capability as Dyligomer II for addition copolymerization, and progressively less capability for reaction with a polyisocyanate. By using two or more of the dyligomers in an intermediate composition, it is possible to control the capability of the intermediate for reaction with a polyisocyanate and for addition copolymerization as desired.

Another structural member according to the invention is indicated generally at 31 in Fig. 9. The member 31 can be produced in the mold 14 of Figs. 2-5, appropriately sized, by placing a piece of the aluminum floor 19 in the mold, introducing the desired amount of a foamable composition, e.g., that of Example 1, into the floor 19, placing a second piece 32 of a different aluminum floor on top of the foamable composition, positioned as shown in Fig. 9, closing the lid of the mold, and clamping the lid shut. It may be desirable, in producing the member 31, for one end of the floor 19 (and of the floor 32) to be higher than the other so that entrapped air, if there is any, can escape from the higher ends of alternate ones of the channels of the floor 32 as the foaming composition moves upwardly. The floor 32 has a plurality of parallel, longitudinally-extending channels, adjacent ones of which have common sidewalls 33 and webs 34 and 35 which are at opposite ends of the sidewalls 33.

Still another structural member is indicated generally at 36 in Fig. 10. The member 36 can be produced in the mold 14 of Figs. 2-5, appropriately sized, by placing a piece of the aluminum floor 19 in the mold, introducing the desired amount of a foamable composition, e.g., that of Example 1, into the floor 19, placing a second piece of a different aluminum floor (not illustrated) on top of the foamable composition, inserting a filler (e.g., an appropriately sized piece of plywood) over the second piece of floor, closing the mold lid, and clamping it in place. The second piece of aluminum floor must have such a configuration that it forms the upper surface of the foamable composition as it expands into contact with the second floor to the shape shown in Fig. 10 for a body 37 of a foamed material, and must be protected, e.g., by a thin sheet of polyethylene, so that it does not adhere to the foam 37. The second piece of aluminum floor is then removed from the mold; a second foamable composition is poured over the body 37 of foam; and a third piece, designated 38 in Fig. 10, of aluminum floor is positioned over the second foamable composition, positioned as shown. A filler, if necessary, is then placed in the mold, over the floor 38, and the lid is closed and clamped. The sizes of the channels in the floors 19 and 38 can be varied as desired, and the floor 38 can be positioned as shown, so that its channels are parallel to the channels in the floor 19, or it can be positioned so that its channels extend at any desired angle to the channels in the floor 19. When the channels are parallel, as shown in Fig. 10, the floor 19 and the floor 38 both increase the strength of the structure mainly when it is supported on members that extend laterally of the channels of the floors. However, when the channels of the floor 38 extend at right angles to the channels of the floor 19, the former

increase the strength of the structure when it is supported on members which extend parallel to the channels of the floor 19 while the latter increase the strength when the structure is supported on members which extend laterally of the channels of the floor 19; this is often a desirable arrangement.

Two steps in the production of still another structural member, designated 39 in Fig. 14, are shown in Figs. 11, 12 and 13. The structural member 39 is made up of a floor 40 having channels 41 which run at a right angle to the paper in Figs. 11 and 12 and a second floor 42 having channels 43 which run parallel to the paper in Fig. 12 and at right angles in Fig. 13. The structural member 39 can be produced in a mold 44 having a bottom 45, sides 46, a top 47 and end walls (not illustrated). The steps carried out in producing the member 44 involve placing the aluminum floor 40 on the bottom of the mold 44, introducing a foamable composition 48 into the mold 44 on top of the floor 40, placing the aluminum floor 42 on top of the foamable composition, and placing a sheet 49 of plywood on top of the floor 42. The assembly which results is shown in Fig. 11. The top 47 of the mold 44 is then closed; the foamable composition 48 expands, forcing the plywood sheet against the top 47 of the mold 44, and undergoes partial cure. The assembly at this stage is shown in Figs. 12 and 13, where the partially cured foam is designated 50. The foamable composition can be that described in Example 1, and it can be introduced into the mold 44 at the rate of 568 g of the composition per 929 cm² of upper surface of webs 51 and 52 of the aluminum floor 40. It is desirable for one of the sides 46 of the mold 44 to be raised above the other during this part of the operation so that air in the channels 43 can flow ahead of the rising foam to one end or the other of the floor 42 and can escape from the channels 43 and from the mold 46, which is highly pervious to air. The lid 47 of the mold 44 is then raised to the position shown in Fig. 11, and the sheet 49 of plywood is removed from the mold 44. A foamable composition, which can be the same as that described in Example 1, is then introduced into the mold 44 on top of the floor 42 at the rate of 568 g of the composition per 929 cm² of upper surface of webs 53 and 54 of the aluminum floor 42. The lid 47 of the mold 44 is then closed again; the foamable composition expands against the lid 47 of the mold 44, and undergoes partial cure. The assembly, which now has its final configuration, is shown in Fig. 14, where the partially cured foam above the floor 42 is designated 56.

It has been demonstrated, by data presented above, that there is cooperation between a thermoset urethane foam and an aluminum floor with which the foam is in intimate contact, and to which it is tightly bonded. The data involve an aluminum floor which had such thin walls that, when it was suspended between two supports which extended transversely of its channels, and were separated from one another by seven inches, a load applied in the center of the member caused it to collapse before available instrumentation indicated the magnitude of the load. Another structure, in which the same aluminum floor was in intimate contact with, and tightly bonded to, a thermoset

urethane foam, when subjected to the same test withstood an applied load of 4650 pounds before failure, while the foam itself, separately produced, failed under a load of only 700 pounds. The foam itself had essentially the configuration of a body 74 of thermoset urethane foam (Fig. 6) in a structural member according to the invention, while the structure in which the aluminum floor was in intimate contact with, and tightly bonded to, a thermoset urethane foam, had essentially the configuration of the Fig. 6 member, except that there was no expanded polystyrene sheet 13, and there was no pad 21.

It will be appreciated that the cooperation between the floor and the thermoset urethane which is discussed in the preceding paragraph is particularly effective when the article tested is supported as described, on members which extend transversely of the channels. The structural member 56 (Fig. 14) is particularly advantageous because it has aluminum floors 40 and 42, which extend essentially at right angles to one another. As a consequence, the load required to cause failure is essentially independent of the angle of the supports to the structural member, and a substantial overhang beyond a support in any direction relative to the floor is acceptable.

A fragment of another structural member according to the invention is designated generally at 56 in Fig. 15, where it is shown in a mold having a bottom 57 and a top 58. The member 56 is composed of a thermoset urethane or other foam 59 disposed between sheet members indicated generally at 60 and 61. The sheet members 60 and 61 have been produced on a brake from galvanized sheet steel about 0.03 mm thick. The sheet steel is broken about every 30 mm to produce a plurality of legs 62, each of which extends across the sheet at about 90° thereto and is about 30 mm long and a plurality of second legs 63, each of which extends across the sheet at about 180° to one of the legs 62 back to the original plane of the sheet, so that the members have a plurality of substantially coplanar strips 64 with legs 62 and 63 between adjacent strips 64. The structural member 56 can be produced in a suitable mold, e.g., identical to that designated 44 in Fig. 11, and having the bottom 57 and the lid 58, by placing the sheet member 60 on the bottom 27 of the mold, with the legs 62 and 63 extending upwardly, introducing a foamable thermosetting composition, e.g., the foamable urethane composition described in Example 1, into the mold on top of the member 60, placing the member 61 on top of the foamable composition, with the legs 62 and 63 extending downwardly, and closing the lid 58. The foamable composition expands and cures to a thermoset condition having the shape shown in Fig. 15, and the foam and the sheet members 60 and 61 are confined in the mold during cure so that the cured foam is tightly adhered to the sheet members 60 and 61.

It will be appreciated from the foregoing discussion that a structural member similar to that designated 56 in Fig. 15, but differing therefrom in that the legs 62 and 63 are not parallel to one another is a preferred structural member according to the instant invention because the load required to cause failure thereof is independent of the direction in which supports extend.

Still another structural member according to the invention is shown in horizontal section in Fig. 16, where it is indicated generally at 65. As shown in Fig. 16, the structural member 65, which is made up of a body 66 of a thermoset foam which is tightly adhered to a longitudinally extending metal reinforcement 67, is in a split, cylindrical mold 68, in which it can be produced. The mold 68 is composed of two mold halves 69 and 70 which abut along mating lines 71 and 72, and can be attached to one another in any suitable manner, as by straps or locks (not illustrated). The metal reinforcement 67 can be produced by bending a sheet member 60 (Fig. 15) so that a plurality of the planar strips 64 form a cylinder with the legs 62 and 63 extending generally radially outwardly from the cylinder. It is not necessary that the ends of the sheet member be fastened together, so long as the metal is deformed sufficiently that it will remain in the cylindrical shape for a short period of time until it is locked in position by the body 66 of thermoset foam.

The structural member 65 can be produced by placing a polyethylene sleeve 73 inside the mold half 69, mating the mold half 70 with the mold half 69, with the sleeve inside, fastening the two mold halves together, supporting the mold in a vertical position with a suitable base material thereunder, e.g., a sheet of polyethylene, introducing a quantity of a foamable, thermosetable material, e.g., the polyol-diisocyanate material of Example 1, into the sleeve 73, lowering the metal reinforcement 67 to the desired vertical position in the mold, supporting the reinforcement at the desired vertical position, e.g., on small wires, and, if necessary, placing a cover on the top of the mold 68. Pins (not illustrated) can also be used to position the metal reinforcement 67 relative to the inner surfaces of the mold halves 69 and 70. The pins, if used, can merely be cut from the exterior of the final post.

In a typical example, the mold 68 has an internal diameter of 4 inches (4.16 cm) and is 7 feet (213.4 cm) long while the metal reinforcement 67 is composed of galvanized steel sheet 0.010 inch (0.254 mm) thick, the strips 64 are about one inch (2.54 cm) wide, the legs 62 and 63 extend outwardly from the cylindrical surface about one inch (2.54 cm), the longitudinal length of the reinforcement 67 is about three feet (91.4 cm), and the reinforcement 67 is supported about one foot (30.5 cm) above the bottom of the mold 68 so that its top is about three feet (91.4 cm) below the top of the mold. A charge of the diisocyanate-polyol of Example 1 sufficient to produce a cured urethane foam having an apparent density ranging from about 20 to about 30 pounds per cubic foot (0.32 to 0.48 g per cm³), in this case, produces a structural member that is admirably suited to serve as a fence post. The reinforcement strengthens the post in the region where breaking usually occurs; the urethane is not attacked by insects. A structural member similar to the member 65, differing only in that it is square or rectangular in cross section and in that the reinforcement extends to within about 6 inches (15 cm) from each end is admirably suited for use as a utility pole cross arm. Such a member can be

produced by the method described above for the production of the member 65, but using a mold having a square or rectangular cross section and metallic reinforcement of a suitable length.

The best structural member presently contemplated for use as a floor for a truck or trailer is indicated generally at 75 in Figs. 18 and 19. The member 75 has a sheet member 76 similar to those designated 60 and 61 in Fig. 15. Referring again to Figs. 18 and 19, the sheet member 76 has a plurality of legs 77, each of which extends across the sheet member 76 at about 90° to the paper in Fig. 18 and is about 30 mm high and a plurality of second legs 78, each of which extends across the sheet member at about 180° to one of the legs 77 back to the original plane of the sheet, so that the members have a plurality of substantially coplanar strips 79 with legs 77 and 78 between adjacent ones of the strips 79. The sheet member 76 also has a plurality of channels 80, each of which is composed of a web 81 and sidewalls 82. The structural member 75 is designed for use as a floor for a refrigerated truck or trailer with floor supports (not illustrated) which extend across the truck or trailer at various points. The channels 80 of the member 75 are spaced from one another so that the webs 81 of different ones of the channels 80 rest on different ones of the floor supports of the truck or trailer, and can be attached thereto by screws which are turned into a foam 83 which is in intimate contact with and firmly bonded to the sheet member 76.

The structural member 75 also has an aluminum floor indicated generally at 84 which is in intimate contact with and firmly bonded to the foam 83. The aluminum floor 84 has a plurality of coplanar strips 85 (Fig. 19) and channels 86 formed by webs 87 and sidewalls 88. The channels 86 extend parallel to the paper in Fig. 18, and at 90° to the paper in Fig. 19. The member 75 can be produced as previously described.

A mold indicated generally at 89 in Figs. 20, 21 and 22 has a bottom 90, two side walls 91 and 92, and an end wall 93 (Fig. 20). The mold 89 is shown in Fig. 21 with a top 94 resting on the sidewalls 91 and 92. A projecting member 95, which is integral with the top 94, extends substantially to the bottom 90 of the mold 89, filling about $\frac{3}{4}$ of the space between the top 94 and the bottom 90. To produce a part in the mold 89, a polyethylene tube (not illustrated) was placed on the bottom 90 of the mold so that its edges extended beyond the side walls 91 and 92, one end extended beyond the end wall 93, and the other end extended beyond a front end 96 of the bottom 90. The top 94 was then placed over the polyethylene tube in the position shown in Fig. 21, and clamped in place; the mold 89 was rotated 90° so that the end wall 93 was down and the front end 96 of the mold was up; and the mixture of MDI and the intermediate composition described in Example 1 was introduced into a cavity 97 (Fig. 21) inside the polyethylene tube until the mixture reached the top of the mold. The mold was then rotated 90° so that the bottom 90 was down; the top 94 was removed, and a top 98 (Fig. 22) was clamped to the mold 89 to form a cavity 99 which was rectangular in cross section, and

about ½ inch by 2 inches by 8 feet. The mixture of MDI and the intermediate composition foamed to fill the cavity 99 and cured. After about 10 minutes, the top 98 was removed from the mold, and a strip of cured material was recovered. The cured material was extremely flexible when it was removed from the mold; it was bent so that the 2 inch faces of the two ends were parallel to one another and there was an arcuate portion between the ends which had a radius of about 18 inches. The strip was supported in this shape for 48 hours, and was then examined. It was no longer flexible; it resisted bending from the shape to which it had been formed, with the ends parallel, and an arcuate portion between, and showed elastic properties after deformation.

It will be appreciated that the phenomena described above indicate that, within ten minutes after the mixture of MDI and the intermediate composition was introduced into the mold 89, a polymer having a molecule in which the moieties derived from the dyligomer were linked to one another through urethane groups and chains formed by the polycondensation of the dyligomer with the polyisocyanate, and, during the next 48 hours, additional chains were formed by the addition polymerization of ethylenic double bonds of the dyligomer with ethylenic double bonds of the triallyl cyanurate. It will also be appreciated that the intermediate of Example 1 contained the reactants which underwent addition polymerization, benzoyl peroxide as a free radical catalyst and cobalt naphthenate as an initiator and that, since the composition was stable at ambient temperature of about 25° C. for extended periods of time, that the proportions of benzoyl peroxide and of cobalt naphthenate present were insufficient to initiate addition polymerization at ambient temperature. However, the exotherm from the isocyanate condensation raised the temperature of the composition enough that the addition polymerization occurred after the isocyanate condensation. This combination of properties is an important characteristic of the intermediate composition of Example 1, and of other intermediate compositions according to the invention.

A window frame according to the invention is indicated generally at 100 in Fig. 23. The frame 100 is composed of side guides 101 and 102, an upper stop 103 and a sill 104. The side guides 101 and 102 are composed of channel members indicated generally at 105 (Fig. 24) bonded to bodies 106 of polymeric material, preferably according to the invention, while the sill 104 is composed of a body 107 of the polymeric material, preferably according to the invention (Fig. 25). The upper stop 103 has the same structure as the side guides 101 and 102, but the body of the polymeric material that is bonded to the channel 105 thereof is not illustrated. The channel members 105 are preferably extruded aluminum or vinyl shapes. The bodies 106 and 107 of the polymeric material are bonded to or integral with one another and are bonded to or integral with the body of the polymeric material that is bonded to the channel 105 of the stop 103 so that the frame 100 has structural integrity. The channel members 105, as shown in Fig. 24, have flat faces 108 and three channels having webs 109 and sidewalls 110

The window frame 100 can be produced in a mold indicated generally at 111 in Fig. 26. The mold 111 comprises a core 112 to which three lengths of channel member 105 are releasably attached, as by a pressure sensitive adhesive (not illustrated). As can be seen better in Fig. 27, the mold 111 also includes side members 113 and 114 which are spaced from the core 112 so that there are cavities between one of the channel members 105 and the side member 113 and between the other of the channel members 105 and the side member 114. There is a similar cavity (not illustrated) between a top member 115 (Fig. 26) of the mold 111 and the channel 105 which extends across the top of the core 112 between the side members 113 and 114. As shown in Fig. 26, there is a sill filler 116 which has the shape of the sill 104 and is positioned in the bottom portion of the mold 111 where it extends between the side members 113 and 114 and between the bottom of the core 112 and a bottom mold member 117, closing the ends of the cavities between the channel members 105 and the side members 113 and 114.

Before a window frame is produced in the mold 111, the surfaces of the mold that will contact the material from which the frame is to be produced are sprayed with the previously described 5 percent solution in naphtha of a silicone caulking material and cellophane tape is adhered with a pressure sensitive adhesive over small openings (e.g., the undersides of joints 118 between adjacent ones of the channels 105) through which the material might otherwise escape. A curable material is then introduced into the cavities between the channel members 105 and the side members 113 and 114 and the top member 115. A polyester or an epoxy casting resin can be used to produce the window frame 100, in which case the casting resin is merely poured into the indicated cavities until they are filled or nearly filled, and allowed to cure. The best material presently contemplated for use in producing the frame 100 is a polymerizable composition according to the instant invention, most desirably one produced by mixing, as described above, 100 parts of Intermediate composition VII, supra, and 47.1 parts of the previously identified, solubilized MDI, and introducing the polymerizable composition which results into the cavities of the mold in the proportion of 0.58 g per cubic centimeter of cavity. If a heavier window frame is desired, a greater proportion of the polymerizable composition can be introduced into the mold cavity and a cover can then be placed over the mold cavity to prevent the escape of the composition therefrom.

The procedure just described produces most of the window frame 100, but without the sill 104. About 5 minutes after the polymerizable composition according to the invention was introduced into the mold 111, the sill filler 116 can be removed from the mold, and replaced by a mold part, preferably one which can be closed, of suitable shape to form the sill 104. A new charge of the same or a different polymerizable composition can then be prepared, and introduced into the mold part in an amount slightly in excess of that required to fill the mold part; the mold part can then be closed,

and the polymerizable composition will force itself into contact with the previously formed frame part. It has been found that a window frame 100 having a strength substantially in excess of that required can be produced in this way.

A fragment of a stud wall is shown in Fig. 28 with the window frame 100 installed between adjacent studs 119, which can be studs in the regular stud pattern in a building (not illustrated) of which they are a part, or can be specially installed at a location where a window to be carried by the frame 100 is required. The side members 113 and 114 can merely be attached, e.g., by a screw or a nail, to one of the studs 119. The frame 100 can then be shimmed as required, and additional fasteners can be inserted into the studs and the frame 100 to mount the frame in a vertical position. Headers 120 and 121 can then be installed above and below the frame 100 to carry studs 122 and 123, as required. The frame 100 can be nailed or otherwise attached to the headers 120 and 121, if desired.

Ultimately, a window sash (not illustrated) in its own frame can be installed in the frame 100. The window sash can be a double hung, casement, awning, slider or the like unit, which can have a channel across its top and opposed channels at its edges, all of which are sized to be received in one of the channels of the members 105, between the sidewalls 110, and one of the side channels can be movable between an extended position and a retracted position in which the window can be advanced into the frame 100 so that the other side channel and the top channel are received between opposed ones of the sidewalls 110 of the frame 100. With the movable channel in the retracted position, the window frame is advanced into the frame 100 until the other side channel and the top channel are received as just described, and the movable channel is moved to its extended position between opposed sidewalls 110, which then prevent removal of the window frame from the frame 110 so long as the movable channel is in its extended position.

In another embodiment of the invention of Fig. 23, the bodies 106 of polymeric material in the side members can extend above the upper stop 103 and below the sill 104 a sufficient distance, and can be so sized that they constitute studs of a wall structure in which the window frames are installed.

It will be appreciated that various changes and modifications can be made from the embodiments of the instant invention that have been described above without departing from the spirit and scope thereof as defined in the attached claims. For instance, Example 1 can be repeated except that the mold 14 is charged with about 1040 g of the composition flowing from the line 28 per 929 cm² of aluminum floor surface, disregarding the area of the legs which extend vertically in Fig. 2 and the area of the horizontally extending surfaces which face downwardly in Fig. 2. A sheet of a polyethylene sheet can then be placed over the polyol/diisocyanate composition, and the lid 17 of the mold can be closed. The urethane then foams until it is compressed between the lid 17 and the

aluminum floor. The final product being a load-bearing floor, roof or the like structure having opposed, substantially parallel major surfaces and a body of a thermoset foam disposed between the major surfaces, one of the opposed major surfaces being a surface of a metal sheet, and there being legs which are structurally integral with the metal sheet and extend into the thermoset foam toward the opposed major surface, and the other of the major surfaces being a surface of the body of thermoset foam, the structure having been produced by confining the metal sheet, the legs and a quantity of a foamable, thermosetable composition which foams and cures to a thermoset condition in a mold, the quantity of the composition being sufficiently great that foaming thereof forces the composition into intimate contact with the legs and the metal sheet and the body of the thermoset foam has an apparent density of at least 8 pounds per cubic foot, and is tightly bonded to the legs and to the metal sheet.

Example 1 can also be repeated except that the expanded polystyrene sheet 13 is replaced by a plywood sheet having the same dimensions which has been wrapped in polyethylene, and has a number of small diameter holes through both the plywood and the polyethylene sheet to vent air that would otherwise be entrapped in the mold as the foamable urethane expanded. After the urethane foams and cures enough to be self supporting, the foamable composition of either of Examples 2 and 3 can be placed on top of the urethane foam in the mold 14, the lid 17, suitably separated from the interior of the mold 14, e.g., by a polyethylene sheet, can be closed, and heat can be supplied to the phenolic composition in the mold to cause it to foam and cure to a thermoset condition. The aluminum floor 11 can be heated dielectrically, or the entire assembly can be placed in a low temperature oven to cause the phenolic to foam and cure.

Other changes and modifications will be apparent to one skilled in the art, and can be made without departing from the spirit and scope of the invention as defined in the appended claims.

I claim:

1. A Dyligomer having the structure



where B is a chemical moiety formed by reactions involving the NCO groups of a diisocyanate having the formula,




and the active hydrogens of OH groups of compounds having the formulas



and A and D are chemical moieties formed by the reactions which formed B, and wherein A and D include, in their structures, at least two active hydrogens which are parts of OH groups and at least one ethylenic double bond.

2. A Dyligomer as claimed in claim 1 wherein B is a moiety which has one of the following structures:



3. A Dyligomer as claimed in claim 1 wherein the OH groups of the compounds having one of the formulas




are alcoholic OH groups.

4. A Dyligomer as claimed in claim 2 wherein the OH groups of the compounds having the formulas




are alcoholic OH groups.


5. A Dyligomer as claimed in claim 2 wherein A has the formula



6. A Dyligomer as claimed in claim 1 wherein A has the formula



7. A Dyligomer as claimed in claim 1 having the structure of Formula 1, below:




Formula 1

where R is an alkyl, hydroxy alkyl, dihydroxy alkyl, alkenyl, or hydroxy alkenyl group having from 2 to 6 carbons.

8. A Dyligomer as claimed in claim 7 where R is alkyl.
9. A Dyligomer as claimed in claim 7 where R is hydroxy alkyl.
10. A Dyligomer as claimed in claim 7 where R is dihydroxy alkyl.
11. A Dyligomer as claimed in claim 7 where R is alkenyl.
12. A Dyligomer as claimed in claim 7 where R is hydroxy alkenyl.
13. A method for producing a thermoset material which comprises producing an intermediate composition by mixing a filler, a catalyst for the reaction of an isocyanate with an active hydrogen, an addition cross-linking material which has at least one ethylenic double bond in its molecule, and a free radical addition polymerization catalyst with a Dyligomer having the structure



where B is a chemical moiety formed by reactions involving the NCO groups of a diisocyanate having the formula,



and the active hydrogens of OH groups of compounds having the formulas



and A and D are chemical moieties formed by the reactions which formed B, and wherein A and D include, in their structures, at least two active hydrogens which are parts of OH groups and at least one ethylenic double bond;

mixing the intermediate composition with an isocyanate component composed of at least one isocyanate and having from 2.0 to 2.17 NCO groups per isocyanate molecule to produce a polymerizable material wherein the ratio of NCO groups to active hydrogens is from substantially 1.0:1 to substantially 1.1:1; and

introducing the mixture of the intermediate composition and the isocyanate component into a mold.

14. A composition which is polymerizable when a suitable amount of an appropriate isocyanate composition, said composition comprising a filler, a catalyst for the reaction of an isocyanate with an active hydrogen, an addition cross-linking material which has at least one ethylenic double bond in its molecule, a free radical addition polymerization catalyst, and a Dyligomer having the structure



where B is a chemical moiety formed by reactions involving the NCO groups of a diisocyanate having the formula,



and the active hydrogens of OH groups of compounds having the formulas



and A and D are chemical moieties formed by the reactions which formed B, and wherein A and D include, in their structures, at least two active hydrogens which are parts of OH groups and at least one ethylenic double bond.

15. A polymeric material having a molecular structure which includes a plurality of chemical moieties derived by copolymerization of an ethylenically unsaturated monomer with, and by reaction

of a diisocyanate or of a polyisocyanate with active hydrogens of, dyligomer molecules having the structure



where B is a chemical moiety formed by reactions involving the NCO groups of a diisocyanate having the formula,



and the active hydrogens of OH groups of compounds having the formulas



and A and D are chemical moieties formed by the reactions which formed B, and wherein A and D include, in their structures, at least two active hydrogens which are parts of OH groups and at least one ethylenic double bond, said polymer having a molecule in which the moieties derived from the dyligomers are linked to one another through urethane groups and chains formed by the polycondensation of the dyligomer with at least one polyisocyanate, and are also linked to one another by chains formed by the addition polymerization of ethylenic double bonds of the dyligomers with ethylenic double bonds of a copolymerizable monomer.

16. A window frame composed of a unitary body of a thermoset polymeric material, said body having an interior opening sized and shaped to receive a window sash to be mounted in said body, and an exterior so sized and shaped that said body can be attached by screws, nails or the like to supporting members of a building which are adjacent a building opening where the window sash is to be installed, and a plurality of channel members bonded to said frame body, said channel members having a plurality of surfaces which are operable, when surfaces of a cooperating window sash are urged thereagainst, to position the cooperating window sash in a predetermined position relative to said frame body, and means which are operably associatable with said channel members and with the cooperating window sash to prevent the window sash from moving from the predetermined position, said last-named means being movable between a locked position in which movement of the window sash from the predetermined position is prevented, and an unlocked position in which such movement of the window sash is not prevented.

17. A window frame as claimed in claim 16 wherein the interior opening sized and shaped to receive a window sash to be mounted in said body is a rectangular opening, and said body has a pair of opposed walls, each of which has a first edge that adjoins the rectangular opening, and a second edge which is parallel to the first edge, and said body has a third wall which has a first edge that adjoins the rectangular opening and a second edge which is parallel to the first edge.




18. A window frame as claimed in claim 17 wherein said channel members are extruded vinyl or aluminum, are embedded in, bonded to, or embedded in and bonded to the first edges of the opposed walls of said body, and have surfaces that adjoin the rectangular opening, and wherein each of said channel members has at least one channel-shaped recess which extends longitudinally thereof and is recessed away from the rectangular opening.

19. A method for producing a window frame which has a top, a bottom and opposed sides, and an opening between the top and the bottom and between the opposed sides for receiving a window sash, which method comprises releasably attaching a plurality of channel members to the exterior of a core which has an exterior shape which corresponds to at least a part of the opening for receiving the window sash, placing a mold part adjacent the core so that, in combination with the core, it forms at least the bottom and two sides of a first mold part for the top of the window frame and one of the channel members is inside the first mold part, placing second and third mold parts adjacent the core so that, in combination with the core, they form at least the bottom and two sides of second and third mold parts for the opposed sides of the window frame and one of the channel members is inside each of the second and third mold parts and there is nothing to prevent the flow of a fluid among the first, second and third mold parts, and introducing into the first, second and third mold parts a composition that is polymerizable under ambient conditions to a thermoset condition.

20. A method as claimed in claim 19 wherein, after the polymerizable material in the first, second and third mold parts has cured to a thermoset condition, a mold for a sill for the window frame is positioned as required to form the sill, and the same or a different composition that is polymerizable under ambient conditions to a thermoset condition is introduced into the sill mold.

21. A method as claimed in claim 19 which additionally includes the steps of releasably attaching a fourth channel member to the exterior of the core, placing a fourth mold part adjacent the core so that, in combination with the core, it forms at least the bottom and two sides of a fourth mold part for the bottom of the window frame, the fourth channel member is inside the fourth mold part, and there is nothing to prevent the flow of a fluid among the first, second, third and fourth mold parts, and introducing the composition that is polymerizable under ambient conditions to a thermoset condition into the fourth mold part.

A Dyligomer is disclosed. The Dyligomer has the structure



46




FIG. 1




FIG. 2




FIG. 3




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8




FIG. 9




FIG. 10




FIG. 11




FIG. 12




FIG. 13















FIG. 14












Fig. 26





Fig. 27



**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☐ BLACK BORDERS
- ☐ IMAGE CUT OFF AT TOP, BOTTOM OR SIDES
- ☐ FADED TEXT OR DRAWING
- ☐ BLURRED OR ILLEGIBLE TEXT OR DRAWING
- ☐ SKEWED/SLANTED IMAGES
- ☐ COLOR OR BLACK AND WHITE PHOTOGRAPHS
- ☐ GRAY SCALE DOCUMENTS
- ☒ LINES OR MARKS ON ORIGINAL DOCUMENT
- ☐ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY
- ☐ OTHER: _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.